

**Part 1      General**

**1.1      SECTION INCLUDES**

- .1      [Floor] [and] [roof] planks.
- .2      Connection [embedments] [and] [hangers].
- .3      Grouting plank joint keys [and end joints].

**1.2      RELATED SECTIONS**

- .1      Section 03 30 00 Cast-in-place Concrete: Concrete [superstructure building frame,] [topping,] [and] [reinforcement].
- .2      Section 03 41 00 - Structural Precast Concrete.
- .3      Section 03 54 00 - Self-leveling Underlayment.
- .4      Section [      -      ]: Masonry load bearing support walls.
- .5      Section 05 12 00 - Structural Steel: Supporting steel [lintels,] [headers,] [      ].

**[OR]**

- .6      Section 05 50 00 - Metal Fabrications: Supporting steel [lintels,] [headers,] [      ].
- .7      Section 07 84 00 – Firestopping.
- .8      Section 07 92 00 – Joint Sealants: Caulking of butt joints of precast units at [exposed underside of floor members.] [      ].
- .9      Section [      -      ]: Interior applied finish.

**1.3      REFERENCES**

- .1      CAN/CSA-A23.1-09/A23.2-09 - Concrete Materials and Methods of Concrete Construction/ Methods of Test for Concrete.
- .2      CSA-A23.3-04 (R2010) - Design of Concrete Structures.
- .3      CSA-A23.4-09 - Precast Concrete - Materials and Construction.
- .4      CSA-A3000-08 - Cementitious Materials Compendium.

- .5 CSA-G40.20-04/G40.21-04 - General Requirements for Rolled or Welded Structural Quality Steel/ Structural Quality Steel.
- .6 CSA-W47.1-09 - Certification of Companies for Fusion Welding of Steel.
- .7 CPCI (Canadian Precast/Prestressed Concrete Institute) Design Manual – 4<sup>th</sup> Edition.
- .8 ASTM A416/A416M-06 - Steel Strand, Uncoated Seven-Wire for Prestressed Concrete.
- .9 ASTM A123/A123M-09 Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
- .10 PCI (Precast Concrete Institute) MNL 116 Manual for Quality Control for Plants and Production of Precast and Prestressed Concrete Products.
- .11 CSA W59-03 (R2008) Welded Steel Construction (Metal Arc Welding).
- .12 CSA W186-M1990 (R2007) Welding of Reinforcing Bars in Reinforced Concrete Construction.
- .13 PCI (Precast Concrete Institute) Manual for Design of Hollowcore Slabs.

#### **1.4 PERFORMANCE REQUIREMENTS**

- .1 Size components to withstand design loads as per the contract documents.
- .2 Maximum Allowable Deflection of Planks as per CSA A23.3 and the contract documents.
- .3 Design components to accommodate construction tolerances, as per relevant CSA codes.
- .4 Precast components to be designed with concrete mix that will achieve 41 [ ] MPa compressive strength at 28 days, with properties according to CSA A23.1 Table 2 for Class N exposure. Slump and air tests not applicable according to CSA A23.1 Clause 8.9.6.
- .5 Grout mix to be 20 MPa at 28 days.

#### **1.5 ADMINISTRATIVE REQUIREMENTS**

- .1 Section 01 31 00: Project management and coordination procedures.
- .2 Coordination:
  - .1 Hollowcore Manufacturer to provide information and drawings to General Contractor to coordinate with other work having a direct bearing on work of this section.
  - .2 General Contractor to coordinate field cut openings with affected section.

- .3 Pre-installation Meetings:
  - .1 General Contractor to convene [one (1)] [ ( ) ] week before starting work of this section.
  - .2 General Contractor to discuss anchor and weld plate locations, sleeve locations, and cautions regarding cutting or core drilling.

**1.6 SUBMITTALS FOR REVIEW**

- .1 Section 01 33 00: Submission procedures.
- .2 Product Data: Indicate standard component configuration, design loads, deflections, and cambers.
- .3 Shop Drawings: Indicate plank locations, connection details, edge conditions, bearing requirements, support conditions, dimensions, openings, [openings intended to be field cut.] and relationship to adjacent materials, to be stamped, signed and dated by a qualified engineer licensed in the province of [ ].
- .4 Installation Data: Fabricator's special installation requirements, indicating special procedures, perimeter conditions requiring special attention, and [ ].

**1.7 SUBMITTALS FOR INFORMATION**

- .1 Section 01 33 00: Submission procedures.
- .2 Sustainable Design:
  - .1 Section [01 35 18]: LEED documentation procedures.
  - .2 Provide required LEED documentation for Product [recycled content] [regional materials] as required by contract documents.

**1.8 CLOSEOUT SUBMITTALS**

- .1 Section 01 78 10: Submission procedures.
- .2 Sustainable Design Closeout Documentation: [ ].

**1.9 QUALITY ASSURANCE**

- .1 Manufacturer to meet requirements of CSA A23.4, including Appendices A and B, together with PCI MNL-116 and 117 and CPCI certification requirements.

- .2 Manufacturer: Certified to Canadian Precast/Prestressed Concrete Institute (CPCI) Precast Concrete Certification Program for Structural, Architectural and Specialty Precast Concrete Products and Systems.
- .3 Perform welding to CSA-W59-03 (R2008) and W186-M1990 (R2007).
- .4 Welder: Qualified within previous [twelve (12)] [ ] months to CSA-W47.1-09.
- .5 Maintain plant records and quality control program during production of precast planks. Make records available upon request.
- .6 Fabricator Qualifications: CPCI Certified Company specializing in manufacturing the Products specified in this section with [documented] experience.
- .7 Erector: Company specializing in performing the work of this section with minimum [five (5)] [ ( )] years [documented experience.]
- .8 Design precast concrete members under direct supervision of a Professional Structural Engineer experienced in design of this Work and licensed at the place where the Project is located.

**1.10 REGULATORY REQUIREMENTS**

- .1 Conform to applicable code for design load and on-site handling requirements.
- .2 Conform to [NBC equivalent thickness], [PCI MNL-124,] [ ] to achieve [ ] hour rating for roof and floor assembly.

**1.11 DELIVERY, STORAGE, AND PROTECTION**

- .1 Section 01 61 00: Transport, handle, store, and protect products.
- .2 Lifting or Handling Devices: Capable of supporting member in positions anticipated during manufacture, storage, transportation, and erection.
- .3 Mark each member with date of production.

**PART 2 Products**

**2.1 ACCEPTABLE FABRICATIONS**

- .1 [ ] [Product] [ ].
- .2 [ ] [Product] [ ].

.3 [ ] [Product] [ ].

## 2.2 MATERIALS

.1 Materials: CSA-A3000, CAN/CSA-A23.1/A23.2.

.2 Tensioning Steel Strands: [ASTM A416/A416M,] [ASTM A421/A421M,] Grade [250] [270] [ ] K of sufficient strength commensurate with member design.

.3 Reinforcing Steel: ASTM A615/A615M, deformed steel bars.

.4 Cement Grout: Minimum compressive strength of < [20] [ ] MPa> << [3,000] [ ] psi>>at 28 days.

## 2.3 ACCESSORIES

.1 Connecting and Supporting Devices: [CSA-G40.20/G40.21 carbon steel;] [ASTM A666 stainless steel;] [ASTM A123/A123M-09 hot dip galvanized] plates, angles, [items cast into concrete,] [items connected to steel framing members,] and inserts; fasteners to ASTM A325.

.2 Core Hole End Plugs: To dam the concrete [or grout].

.3 Bearing Pads: [High density plastic, <[3] [ ] mm><<[1/8] [ ] inch>> thick, smooth on [one side.] [both sides.], [masonite hard board], [ ].

.4 Shims: [Plastic.] [Steel.]

## 2.4 FABRICATION

.1 To commence upon receipt of approved shop drawings and schedules.

.2 Conform to CSA-A23.4.

.3 Embed anchors, inserts, plates, angles, and other items at locations indicated on approved drawings.

.4 Provide openings required by other sections, at locations indicated on approved drawings.

## 2.5 COMPONENTS

.1 Nominal Thickness: <[152] [203] [254] [305] [330] [356] [ ] mm><<[6] [8] [10] [12] [13] [14] [ ] inches>>.

.2 Nominal Plank Width: <[1 220] [ ] mm> <<[48] [ ] inches>>.

## **2.6 FINISHES**

- .1 Plant Finish: Top surface: as extruded or required by contract documents or floor system design requirements.
- .2 Plant Finish: Bottom surface: as extruded; may contain small surface holes caused by small air bubbles, minor chipping, or spalling at edges or ends, without major discolouration.
- .3 Connecting and Supporting Steel Devices: [Prime painted.] [Hot dip galvanized.] [Electroplated.] [Unfinished.]

## **2.7 FABRICATION TOLERANCES**

- .1 Conform to CSA A23.4.

## **2.8 SOURCE QUALITY CONTROL [AND TESTS]**

- .1 Provide [testing] [and] [analysis] of site placed concrete and grout as required by contract documents.
- .2 Provide shop [inspection] [and] [testing] for stressing strands.
- .3 Test samples in accordance with specified standards.

## **PART 3 Execution**

### **3.1 EXAMINATION**

- .1 General Contractor to verify that site conditions are ready to receive work and field measurements are as indicated on approved drawings.
- .2 Verify supporting structure is ready to receive work.

### **3.2 ERECTION**

- .1 Erect members without damage to structural capacity, shape, or finish. Replace or repair damaged members.
- .2 Align and maintain uniform horizontal and end joints, as erection progresses.
- .3 General Contractor to maintain any temporary bracing if required for the supporting structure [components] [or] to avoid any rotation or excessive deflections of the supporting components.
- .4 Install bearing pads at bearing ends of planks [as indicated].

- .5 Adjust differential camber between precast members to tolerance before final attachment [and grouting].
- .6 Adjust differential elevation between precast members to tolerance before final attachment [and grouting].
- .7 Grout plank joints, trowel smooth.
- .8 Transition differential elevation of adjoining planks with grout to a maximum slope of [ ] [as required].
- .9 Secure units in place according to erection drawings. Perform welding in accordance with [CSA-W59.] [CSA-W186.]
- .10 Field cut holes and openings up to [150 mm] [6 inches] in diameter to be cored or drilled by the trade requiring them, subject to the approval of the hollowcore slab manufacturer.
- .11 Openings larger than [150 mm] [6 inches] to be located on shop drawings at time of approval and to be provided in the shop.
- .12 Do not cut any reinforcing without prior approval of the precast slab manufacturer and engineer.

### **3.3 ERECTION TOLERANCES**

- .1 Section 01 73 00: Tolerances.
- .2 Erect members level and plumb, within allowable tolerances.
- .3 Erect to the tolerances as specified in CSA A23.4.

### **3.4 CLEANING**

- .1 Section 01 74 00: Cleaning installed work.
- .2 Clean weld marks, dirt, or blemishes from surface of exposed members, caused by the work of this trade.
- .3 Clean field welds with wire brush and touch up with [primer] [galvanized] paint.
- .4 Upon completion of the work in this section, all surplus materials and debris shall be removed from this site.

### **3.5 PROTECTION OF FINISHED WORK**

- .1 Section 01 78 40: Protecting installed work.
- .2 Protect members from damage caused by field welding or erection operations performed by the work of this trade.
- .3 Provide non-combustible shields during welding operations, as required.

**END OF SECTION**